AGENDA ITEM 5

APPENDIX I

2019/0051/DET

PLANS

Forest Enterprise Scotland

Managing the National Forest Estate

Overall Plan

Author: Kelly McKellar

Scale @ A3: 1:10,000

Date: 04/02/2019

Legend

Blocks


Forest Roads

0 0.0475.095 0.19

Forest Estate is responsibly managed to the

UK Woodland

Forest Roads _



C7*+

**

*

**



**


**

**


**

raig V . 6. 0

1.4.



Blocks			
orest Roads			
— Forest F	Roads		







AERIAL MAST NOTES:

- This drawing is to be read in conjunction with the Specification and all relevant Engineers drawings. All brand named products may be replaced with equal products subject to approval by the designer.
- 2. All dimensions are in millimetres unless stated otherwise.
- 3. All levels are in metres unless stated otherwise.
- 4. TIMBER All graded timber to be supplied with appropriate CE marking. Where specified holes to be drilled before treatment. All softwood except Larch heartwood to be treated with Tanalith-E preservative. Cuts and holes made on site to be treated with Ensele 3450. All timber to be from a sustainable source FSC certified or equivalent. Certification must be provided before timber will be approved. Handrail timbers must span at least 3 posts and joins on adjacent rails must not be on the same post. Allowance for cutting waste is the contractors responsibility.
- All concrete to comply with EN206:BS8500. Mix RC35, S2 slump, 280kg cement and water cement ratio 0.6. Surface finish, all hidden faces F1, visible faces F5.
- A plumb line should be set up between first and last handrail posts of each span to ensure the handrails are horizontal and do not show dead load deflection.
- 5. Ground bearing capacity to be assessed and approved by the Engineer.
- 6. All bolts, screws and washers to be spun galvanised.
- Steel bridge kit from Haley Engineering, supplied with CE Marking. All steelwork & coach screws to be hot dip galvanised in accordance with BS EN ISO 1461:2009
- Nuts to be tack welded to 'U' bolt shafts after final tightening, wire brush cleaned and galvafroid welded area.
- Should construction be delayed for more then 1 year from the date of issue, please contact CETS for the latest drawing revision.
- 10. The new bridges are located at approx OS grid reference NH 984 071.

Revision	Date	Changes		Drawn Checked			
Drawing St	tatus:	CONSTR	UCTION				
	REST	RY COMM	ISSION SO	COTLAND			
CIV	IL ENG	INEERING	TECHNICA	L SERVICES			
E F	orestry ommissio	231 Corsto Edinburgh	House, rphine Road, , EH12 7AT 0 067 6971				
Job Title:		UTSI'S I	BRIDGE				
	GLENMORE						
		-	REGION				
		NUKIN	REGION				
SITE PLAN							
Drawn:	KMcK		Job No: CETS/1621	Date: 10 Mar 2019			
Checked:			Scales: 1:200				
Drawing N	Drawing No: CETS/1621/03						
	-		Т	his drawing is protected by Copyright			







LOCATION PLAN

AERIAL MAST NOTES:

- 1. This drawing is to be read in conjunction with the Specification and all relevant Engineers drawings. All brand named products may be replaced with equal products subject to approval by the designer.
- 2. All dimensions are in millimetres unless stated otherwise.
- 3. All levels are in metres unless stated otherwise
- 4. TIMBER All graded timber to be supplied with appropriate CE marking. Where specified holes to be drilled before treatment. All softwood except Larch heartwood to be treated with Tanalith-E preservative. Cuts and holes made on site to be treated with Ensele 3450. All timber to be from a sustainable source FSC certified or equivalent. Certification must be provided before timber will be approved. Handrail timbers must span at least 3 posts and joins on adjacent rails must not be on the same post. Allowance for cutting waste is the contractors responsibility
- 4. All concrete to comply with EN206:BS8500. Mix RC35, S2 slump, 280kg cement and water cement ratio 0.6. Surface finish, all hidden faces F1, visible faces F5.
- 5. A plumb line should be set up between first and last handrail posts of each span to ensure the handrails are horizontal and do not show dead load deflection.
- 6. Ground bearing capacity to be assessed and approved by the Engineer.
- 7. All bolts, screws and washers to be spun galvanised.
- 8. Steel bridge kit from Haley Engineering, supplied with CE Marking. All steelwork & coach screws to be hot dip galvanised in accordance with BS EN ISO 1461:2009
- 9. Nuts to be tack welded to 'U' bolt shafts after final tightening, wire brush cleaned and galvafroid welded area.
- 10. Should construction be delayed for more then 1 year from the date of issue, please contact CETS for the latest drawing revision.
- 11. The new bridges are located at approx OS grid reference NH 984 071.

С 13/06/19 B 20/05/19 Α 15/04/19 Revision Date Drawing Status:

Flood levels adjusted.
Change to 1 in 200 year flood level.
Deeper aerial mast sections.
Changes

GW GW GW GW BM GW Drawn Checked

CONSTRUCTION

FORESTRY COMMISSION SCOTLAND

CIVIL ENGINEERING TECHNICAL SERVICES



Forestry and Land Scotland Coilltearachd agus

Silvan House, 231 Corstorphine Road, Edinburgh, EH12 7AT



Drawing Title

GW

Checked

Tel: 0131 370 5121



Fearann Alba

UTSI'S BRIDGE GLENMORE NORTH REGION

Job No: CETS/1621

Scales: 1:100; 1:50; 1:20; 1:10; 1:5

AERIAL-MAST BRIDGE 2 No. 14m CLEAR SPANS **GENERAL LAYOUT**


CETS/1621/01

С This drawing is protected by Copyrigh

Revision:

Date: 30 Nov 2018


5	926	326	326	326		•		•		·						
					 •	•	•	•	,	•		•	•	•		
5	97C	326	326	325	 •	•		•	•	•		•		•		
5	32C	356	326	355												
-		r		늈	 Å.,		4		nana		ww	war	Ľ)= -	f	
		F	77	Ţ	7	\sum										
				1	_	А	1									




		Hardwo	are Schedule (Extra over Bridge Kit)		
MARK	PART	FIXING	ТҮРЕ	LENGTH	No
1	Deck boards & Rails	Screws	6mm Ø cross-headed quick start csk wood screws, stainless steel	100	1020
2	Holding down Bolts	Threaded Bar	20mm Ø plated threaded bar with 3 no. hex nuts and Form G washer	750	12
3	Runner	Coach Screw	Galvanised 6mm Ø	60	128
4	Ramp post bolts	Coach Bolt	Galvanised 12mm Ø with 1 no. hex nut and 2 no. Form G washers	250	12
5	HD screws into sleepers	Coach Screw	Galvanised 16mm Ø with Form A washer	75	9
6	Ramp tread fixings	Screws	6mm Ø cross-headed quick start csk wood screws, stainless steel	250	100
7	Stringer angle anchors	Threaded Bar	12mm Ø plated threaded bar with 1 no. Form A washer	200	8
8	Stringer angle bolts	Coach bolt	Galvanised 12mm Ø with 1 no. hex nut and 2no. Form G washers	125	16
9	Stringer angle to plate	Coach screw	Galvanised 12mm Ø	60	8
10	Timber plate to ramp angle	Coach bolt	Galvanised 12mm Ø with 1 no. hex nut 1 no Form A washer, and 1 no. Form G washer	75	10
11	Ramp support angle	Black bolt Gr 4.6	Plated 16mm Ø with 1 no hex nut and Form A washer	60	12


Contractor to estab	lish exact dimens	Fimber S	chedule and quantities	- Refer to before cutting a	Note 4 nd treating, and t	o make	allowance for cutting waste.
Part	Species	Grade	Finish	Treatment	Size (mm)	No.	Notes
Deck Planks	Larch/Fir	C24	Sawn	Tanalith E	150 x 50 1875 long	176	With Non-Slip Inserts
Runners	Oak	-	Sawn	None	75x45 28000 long	4	
Bridge Posts	Larch	C24	Sawn	Tanalith E	100x100 1970 long	56	45° cut one end.
End Posts	Larch	C24	Sawn	Tanalith E	100x100 1940 long	8	30° cut one end.
Top Rails	Larch heartwood	GS	Dressed	None	150x40 28500 long	2	Fix to a minimum of three posts.
Side Rails	Larch heartwood	GS	Dressed	None	100×50 28500 long	6	Fix to a minimum of three posts.
Kerbs	Larch heartwood	GS	Dressed	None	150x50 28500 long	2	Fix to a minimum of three posts.
Sleepers	Oak	D40	Sawn	None	250x150 2500 long	3	
Ramp Posts	Larch	C24	Sawn	Tanalith E	100x100 1525 long	6	30° cut one end.
Ramp 1 - Top Rail	Larch heartwood	GS	Dressed	None	150x40 2890 long	2	
Ramp 1 - Side Rails	Larch heartwood	GS	Dressed	None	100×50 2890 long	8	
Ramp 1 - Stringers	Larch/Fir	GS	Sawn	Tanalith E	175x75 2990 long	4	
Ramp 2 - Top Rail	Larch heartwood	GS	Dressed	None	150x40 1695 long	2	
Ramp 2 - Side Rails	Larch heartwood	GS	Dressed	None	100x50 1695 long	8	
Ramp 2 - Stringers	Larch heartwood	GS	Dressed	None	175x75 1795 long	4	
Ramp Deckboards	Larch/Fir	GS	Sawn	Tanalith E	250x50 1900 long	16	Screw on GRP non-slip strip on top.
Ramp Support Angle Plate	Larch/Fir	GS	Sawn	Tanalith E	100x50 2000 long	2	Bolt onto ramp support angle.
Tread Supports	Larch/Fir	GS	Sawn	Tanalith E	250×150×75	32	
Dwangs	Larch/Fir	GS	Sawn	Tanalith E	150×50×1000	8	

KEY PLAN



Galvanised steel stringer 125x75x8RSA, 75mm lon 0.5x1.0x1.0 Gabion bask 1.0x1.0x1.0 Gabion baske





LOCATION PLAN

AERIAL MAST NOTES:

- 1. This drawing is to be read in conjunction with the Specification and all relevant Engineers drawings. All brand named products may be replaced with equal products subject to approval by the designer.
- 2. All dimensions are in millimetres unless stated otherwise.
- 3. All levels are in metres unless stated otherwise.
- 4. TIMBER All graded timber to be supplied with appropriate CE marking. Where specified holes to be drilled before treatment. All softwood except Larch heartwood to be treated with Tanalith-E preservative. Cuts and holes made on site to be treated with Ensele 3450. All timber to be from a sustainable source FSC certified or equivalent. Certification must be provided before timber will be approved. Handrail timbers must span at least 3 posts and joins on adjacent rails must not be on the same post. Allowance for cutting waste is the contractors responsibility
- 4. All concrete to comply with EN206:BS8500. Mix RC35, S2 slump, 280kg cement and water cement ratio 0.6. Surface finish, all hidden faces F1, visible faces F5.
- 5. A plumb line should be set up between first and last handrail posts of each span to ensure the handrails are horizontal and do not show dead load deflection.
- 6. Ground bearing capacity to be assessed and approved by the Engineer.
- 7. All bolts, screws and washers to be spun galvanised.
- 8. Steel bridge kit from Haley Engineering, supplied with CE Marking. All steelwork & coach screws to be hot dip galvanised in accordance with BS EN ISO 1461:2009
- 9. Nuts to be tack welded to 'U' bolt shafts after final tightening, wire brush cleaned and galvafroid welded area.
- 10. Should construction be delayed for more then 1 year from the date of issue, please contact CETS for the latest drawing revision.
- 11. The new bridges are located at approx OS grid reference NH 984 071.

		1						
Α	15/04/19	Bridge deck raised.			вм	GW		
Revision	Date	Changes			Drawn	Checke		
Drawing S	ratus:	CONSTRUCTION	ON					
Client:								
FC	OREST	RY COMMISSIO	N SCO	DTLA	N)		
CI\	/IL ENG	SINEERING TECH	NICAL	SER	VIC	ES		
	A	Forestry and		Silv	an Ho	use.		
		Land Scotland		orstorph	ine R	oad,		
		Coilltearachd agus	Edi	inburgh,	EH12	7AT		
٦	IT	Fearann Alba		Tel: 0131	370	5121		
Job Title:								
		UTSI'S BRIDO	GE					
		GLENMOR	5					
		OLEINMORI	5					
		NORTH REGI	ON					
Drawing T								
AERIAL-MAST BRIDGE								
2 No. 14m CLEAR SPANS								
		RAMP DETAI	LJ					
Drawn:	GW	Job No:	TS/1621	Date: 30	Nov 20	18		
Drawn: Checked:	GW	Job No: CE Scales:		30	Nov 20	18		
	10:	Job No: CE Scales:	TS/1621	30	Nov 20 Revisior			

Bridge Kit to include

	No.
	24
	6
g	64
8mm thick drawn m	4
ircular U bolts ircular U bolts	288
ular U bolts	128
ong	2
l plates	
vanised HD nØ hole.	12
angle fixings ng	16
ets	9
ets	13

A1 - DO NOT SCALE